AD-A244 645

Final Report February 1990

EVT 5-90

DTIC SELECTE JAN 17, 1992

TRANSPORTABILITY TESTING

OF

6,000-GALLON WATER DISTRIBUTOR

DISTRIBUTION STATEMENT A

Approved for public releases

Distribution United

92-01517

Distribution Unlimited

Prepared For:

U.S. Army Tank-Automotive Command

ATTN: AMSTA-ISFA Warren, MI 48397-5000 92 1 16 088

US ARMY
ARMAMENT
MUNITIONS
CHEMICAL COMMAND

EVALUATION DIVISION SAVANNA, ILLINOIS 61074-9639

US ARMY DEFENSE AMMUNITION CENTER AND SCHOOL

AVAILABILITY NOTICE

A complimentary copy of this report is furnished each attendee on automatic distribution. Additional copies or authority for reprinting may be obtained by written request from Director, U.S. Army Defense Ammunition Center and School, ATTN: SMCAC-DEV, Savanna, IL 61074-9639.

DISTRIBUTION INSTRUCTIONS

Destroy this report when no longer needed. Do not return.

* * *

Citation of trade names in this report does not constitute an official endorsement.

* * *

The information contained herein will not be used for advertising purposes.

UNCLASSIFIED

SECUIPITY CLASSIFICATION OF THIS PAGE

REPORT DOCUMENTATION PAGE					Form Approved OMB No. 0704-0188			
1a. REPORT S UNCLAS	ECURITY CLASS	SIFICATION		1b. RESTRICTIVE MARKINGS				
		N AUTHORITY	•	3 DISTRIBUTION	3. DISTRIBUTION/AVAILABILITY OF REPORT			
26. DECLASSI	CATION / DOW	VNGRADING SCHEDU	LE	UNLIMITED				
4. PERFORMIN	IG ORGANIZAT	ION REPORT NUMBE	R(S)	5. MONITORING ORGANIZATION REPORT NUMBER(S)				
EVT 5-	90							
6a. NAME OF PERFORMING ORGANIZATION U.S. Army Defense Ammunition Center and School SMCAC-DEV				7a. NAME OF MONITORING ORGANIZATION				
6c. ADDRESS	City, State, an	d ZIP Code)		7b. ADDRESS (City, State, and ZIP Code)				
ATTN: SMCAC-DEV Savanna, IL 61074-9639								
ORGANIZA		Army Tank-	8b. OFFICE SYMBOL (If applicable)	9. PROCUREMENT INSTRUMENT IDENTIFICATION NUMBER				
	tive Comma City, State, and		AMSTA-ISFA	10 SOURCE OF	UNDING NUMBER	<u> </u>		
	AMSTA-ISE			PROGRAM	PROJECT	TASK	WORK UNIT	
	, MI 4839			ELEMENT NO.	NO.	NO.	ACCESSION NO.	
	11. TITLE (Include Security Classification) Transportability Testing of 6,000-Gallon Water Distributor							
12. PERSONAL			· · · · · · · · · · · · · · · · · · ·					
	McIntosh,							
13a. TYPE OF REPORT 13b. TIME COVERED FROM TO TO			14. DATE OF REPORT (Year, Month, Day) 15. PAGE COUNT 1990 February 19					
16. SUPPLEMENTARY NOTATION								
17.	COSATI	CODES	18. SUBJECT TERMS (Continue on revers	e if necessary and	identify	by block number)	
FIELD	GROUP	SUB-GROUP						
19. ABSTRACT	(Continue on	reverse if necessary	and identify by block n	umber)		-		
The U.S. Army Defense Ammunition Center and School (USADACS), Evaluation Division (SMCAC-DEV), was tasked by the U.S. Army Tank-Automotive Command (TACOM), AMSTA-ISFA, to perform a rail impact test for the 6,000-Gallon Water Distributor fabricated by E. D. Entyre and Co. From information provided, the Storage and Outloading Division (SMCAC-DEO), developed tiedown procedures for transporting the 6,000-Gallon Distributor on a flatcar. These procedures were then tested to Association of American Railroads (AAR) Rail Impact test requirements. The 6,000-Gallon Water Distributor, as tied down on a flat car, passed these requirements. The results of these tests are contained in this report. 20. DISTRIBUTION/AVAILABILITY OF ABSTRACT Security CLASSIFICATION UNCLASSIFIED UNCLASSIFIED SAME AS RPT. DIIC USERS 21. ABSTRACT SECURITY CLASSIFICATION UNCLASSIFIED UNCLASSIFIED SAME AS RPT. DIIC USERS								
THOMAS			uation Division	815-273-8	928	SM	CAC-DEV	

DD Form 1473, JUN 86

Previous editions are obsolete

SECURITY CLASSIFICATION OF THIS PAGE

U.S. ARMY DEFENSE AMMUNITION CENTER AND SCHOOL Evaluation Division Savanna, IL 61074-9639

REPORT NO. EVT 5-90


TRANSPORTABILITY TESTING OF

6,000-GALLON WATER DISTRIBUTOR

TABLE OF CONTENTS

PART					PAGE NO.
1.	INTE	ODUCTION	 	• • • • • • •	 1-1
	Α.	Background	 	• • • • • • • • •	 1-1
	В.	Authority	 	• • • • • • •	 1-1
	C.	Objective	 		 1-1
	D.	Conclusions	 		 1-1
	E.	Recommendation.	 		 1-1
2.	ATTE	NDEES	 		 2-1
3.	TEST	PROCEDURES	 		 3-1
4.	TEST	RESULTS	 		 4-1
5.	TEST	PLANS	 		 5-1
6.	PHOT	OGRAPHS	 		 6-1





INTRODUCTION

- A. <u>BACKGROUND</u>. The U.S. Army Defense Ammunition Center and School,

 Evaluation Division (SMCAC-DEV), was tasked by TACOM, AMSTA-ISFA, to perform a
 rail impact test for the 6,000-Gallon Water Distributor fabricated by E. D.

 Entyre and Co. From information provided, the Storage and Outloading Division
 (SMCAC-DEO), developed tiedown procedures for transporting the 6,000-Gallon

 Water Distributor on a flatcar. These procedures were then tested to AAR Rail
 Impact test requirements.
- B. <u>AUTHORITY</u>. This test was conducted in accordance with mission responsibilities delegated by the U.S. Army Armament, Munitions and Chemical Command (AMCCOM), Rock Island, IL 61299-6000. Reference is made to Change 4. October 1974, to AR 740-1, 23 April 1971, Storage and Supply Operations; AMCCOMR 10-17, 13 January 1986, Mission and Major Functions of U.S. Army Defense Ammunition Center and School.
- C. <u>OBJECTIVE</u>. The objective of this test was to determine if the 6,000-Gallon Water Distributor was transportable on a rail flatcar when tested to AAR Rail Impact test requirements and the developed tiedown procedure.
- D. <u>CONCLUSIONS</u>. The tiedown procedure for the 6,000-Gallon Water Distributor satisfied the AAR Rail Impact test requirements.
- E. <u>RECOMMENDATIONS</u>. It is recommended that the tiedown procedure for transportation of the 6,000-Gallon Water Distributor be approved.

ATTENDEES

Mr. A. C. McIntosh, Jr. Test Engineer AV 585-8989 Comm 815-273-8989

Mr. Dave Valant
Electronics Technician
AV 585-8988
Comm 815-273-8988

Mr. Ralph Arnold Industrial Engineer AV 585-8073 Comm 815-273-8073

Mr. Patrick O'Brien 815-732-2116

Mr. James K. Bertsch 815-732-2116

Director
U.S. Army Defense Ammunition Center
and School
ATTN: SMCAC-DEV
Savanna, IL 61074-9639

Director
U.S. Army Defense Ammunition Center
and School
ATTN: SMCAC-DEV
Savanna, IL 61074-9639

Director
U.S. Army Defense Ammunition Center
and School
ATTN: SMCAC-DEO
Savanna, IL 61074-9639

E. D. Entyre and Co. 1333 S. Daysville Rd. Oregon, IL 61061

E. D. Entyre and Co. 1333 S. Daysville Rd. Oregon, IL 61061

TEST PROCEDURES

RAIL IMPACT. The test load or vehicle should be positioned in/on a railcar. For containers, the loaded container shall be positioned on a container chassis and securely locked in place using the twist locks at each corner. The container chassis shall be secured to a railcar. Equipment needed to perform the test includes the specimen (hammer) car, five empty railroad cars connected together to serve as the anvil, and a railroad locomotive. These anvil cars are positioned on a level section of track with air and hand brakes set, and with the draft gear compressed. The locomotive unit pulls the specimen car several hundred yards away from the anvil cars and, then, pushes the specimen car toward the anvil at a predetermined speed, disconnects from the specimen car about 50 yards away from the anvil cars, and allows the specimen car to roll freely along the track until it strikes the anvil. This constitutes an impact. Impacting is accomplished at speeds of 4, 6, and 8 mph in one direction and at a speed of 8 mph in the opposite direction. The 4 and 6 mph impact speeds are approximate; the 8 mph speed is a minimum. Impact speeds are to be determined by using an electronic counter to measure the time required for the specimen car to traverse an 11-foot distance immediately prior to contact with the anvil cars.

TEST RESULTS

RAIL IMPACT DATA

TEST NO. 1 DATE: 1 November 1989

TEST SPECIMEN: 6,000-Gallon Water Distributor on a flatcar.

TEST CAR NO. BN600082 LT. WT. 47,900 pounds


LADING AND DUNNAGE WT. 15,000 pounds

TOTAL SPECIMEN WT. 62,900 pounds

BUFFER CAR (5 CARS) WT. 250,000 pounds

IMPACT NO.	END STRUCK	VELOCITY (MPH)	IMPACT FORCE	REMARKS
1	forward	4.60		no damage
2	forward	6.57		no damage
3	forward	8.57		no damage
4	reverse	8.72		no damage

TEST PLANS



(DISTRIBUTED EQUALLY ON CAP (5). (CONCENTRATED ON CAP (5) AT ONE POINT CENTERED BETWEEN LEGS (3). 4,200 LBS 2,100 LBS

60


KEY NUMBERS


- 1) 4" × 4" × 30" (1 REQD).
- 2 2" x 6" x 40" (2 REOD). HAIL TO 1 W/6-12d HAILS. HAIL TO 3
 AND 4 W/2-12d NAILS EACH.
- 3 0 4" x 4" x 55" (2 REQD). TOENA!L TO () A:D (9 W/4-16d HAILS
- 4 4 × 4 × 68 4 (2 REOD). DOUSLE BEVEL EACH END. SEE "DETAIL PIECE 4" FOR BEVEL CUTS REQUIRED. TOENAIL TO 1 W/2-16d NAILS. NAIL TO (1) W/4-16d NAILS AFTER ASSEMBLY (1) THRU 9) HAS BEEN LOCATED CN CAR AND (1) HAS BEEN NAILED TO CAR FLOOR.
- (3) 2" x 6" x 40" (2 REQD). NAIL TO (1) AND (2) W/5-12d HAILS EACH AND TO (4) AND (6) W/2-12d HAILS EACH JOINT.
- 6 0 4 × 4 × 68 (4 REOD). DOUBLE BEVEL EACH END. SEE DETAIL PIECE 6 *
 FOR EEVEL CUTS REQUIRED. TCENAIL TO 2 W/4-16d NAILS. TOENAIL
 TO 9 W/4-16d NAILS BEFORE ASSEMBLY (1) THRU 9) HAS BEEN LOCATED UNDER ITEM AND 9 HAS BEEN NAILED TO CAR FLOOR.
- 7 2" x 4" x 68" (1 REQD). HAIL TO 3 AND 4 W/3-12d NAILS EACH
- (9 ⊕ 2" × 6" × 8"-8" (2 REOD). NAIL TO CAR FLOOR W/I-30d NAIL EVERY 8".
- 2" x 6" x 12" (4 REOD). POSITION AGAINST 6 AND NAIL TO 9 W/4-30d KAILS.
- 1) 2" x 6" x 24" (2 REQD). HAIL TO CAR FLOOR W/5-30d WAILS.

 2" x 6" x 12" (2 REQD). POSITION AGAINST (4) AND HAIL TO (1) W/4-3Cd


 HAILS.

NOTE # : THE LENGTHS SPECIFIED FOR 3. 4. 6. AND 9 ARE BASED ON AN ASSEMBLY HEIGHT OF 52%. FOR EACH ONE INCH (1%) VARIATION IN THE ASSEMBLY HEIGHT, THE SPECIFIED OVERALL LENGTHS OF THESE PIECES WILL BE





& TANDEM to & STANCHION : 26'-5 BASE OF STANCHION BASE OF STANCHION = 8'-8" & TANDEM TO



PHOTOGRAPHS







Photo No. 1 (90-1528) This photo shows the 6,000-Gallon Water Distributor tied down on standard friction stanchion provides forward vertical support. Landing gear is not designed to support the semitraller draft flatear. The Distributor is secured to the flatear with eight 3/8-inch wire rope cables. The in a transportation environment.



(90-1534) This photo shows the 6,000-Gallon Water Distributor loaded on a standard flatcar. The landing gear Photo No. 2 (90-1534) This photo shows the 6,000-Gallon Water Distributor loaded on A stanchion supports the forward end of the trailer in a transportation environment. Will not support the trailer while being transported by rail.



Copy available to DTIC does not parmit fully liable reproduction



Copy available to DTIC does not parmit tally legible reproduction